

Municipal Advisory Board

Established May 1, 2008 at the University of Texas, Arlington



MAB Guidelines for PE 4710 Pipe Bursting of Potable Water Mains MAB-5 (2025)

Refer to the MAB Website to ensure the use of the current version
www.plasticpipe.org/MABpubs

2nd edition re-approved as is by MAB on May 2, 2025, at the Municipal Utilities District, Omaha, NE

1st edition approved by MAB at the City of Fort Wayne, Indiana
© **Plastics Pipe Institute, 2019, 2025**

FOREWORD

This guide was developed by the Municipal Advisory Board (MAB) and published with the help of the members of the Plastics Pipe Institute, Inc. (PPI).

This document is intended as a guide for engineers, users, contractors, code officials, and other interested parties for use in the design, construction, and installation of high-density polyethylene (HDPE) pressure water piping systems. The local utility or engineer may need to modify this model specification to adapt the document to local conditions, operations, and practices.

This guide has been prepared by MAB members and associates as a service to the water industry. The information in this document is offered in good faith and believed to be accurate at the time of its preparation, but is offered "as is" without express or implied warranties, including WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Any reference to a specific manufacturer's product is merely illustrative, and not intended as an endorsement of that product. Reference to or testing of a proprietary product should not be construed as an endorsement by the MAB or PPI, which do not endorse the proprietary products or processes of any manufacturer. Users are advised to consult the manufacturer for more detailed information about the specific manufacturer's products. The information in this document is offered for consideration by industry members in fulfilling their own compliance responsibilities. MAB and the PPI assume no responsibility for compliance with applicable laws and regulations.

The MAB serves as an independent, non-commercial adviser to the Municipal & Industrial (M & I) Division of the PPI. Once adopted, MAB will consider revising this specification from time to time, in response to comments and suggestions from users of the model specification. Please send suggestions of improvements to Camille George Rubeiz, PE, F.ASCE, at crubeiz@plasticpipe.org.

ACKNOWLEDGEMENTS (2019)

The Municipal Advisory Board would like to acknowledge the excellent contributions of the MAB Task Group for developing and leading this project.

Todd Grafenauer	Murphy Pipelines, Chair
Jessie Allen, PE	City of Arlington, TX
Alan Ambler, PE	AM Trenchless, FL
Alan Atalah, PE	Bowling Green State University, OH
Marisa Boyce, PE	EBMUD, CA
Ryan McKaskle, PE	City of Tulsa, OK
Camille Rubeiz, PE	Plastics Pipe Institute, TX
Andrew Schipper, PE	City of Ft. Wayne, IN
Matthew Wirtz, PE	City of Ft. Wayne, IN
Eric Shaffer, PE	City of Duluth, MN

MUNICIPAL ADVISORY BOARD MEMBERS

UTILITIES

1. **Marisa Boyce, PE**, EBMUD, CA
2. **Angelo Dupont**, Arlington Water Utilities, TX
3. **Dale Harmon**, Boothbay Region Water Dist., ME
4. **Jacob Nakano**, City Utilities, MO
5. **Nelson P. Jacome, PE**, Miami-Dade WASD, FL
6. **Jeff Kyle, PE**, City of Austin, TX
7. **Cheryl Wilson, PE**, City of Tulsa, OK
8. **Evan Martin, PE**, MUD-Omaha, NE
9. **Lance Rothe, PE**, SAWS, TX
10. **Kaitlyn Saucedo**, City of Round Rock, TX
11. **Howard Smith, PE**, City of Duluth, MN
12. **Matthew Wirtz, PE**, City of Ft Wayne, IN

PPI, Camille Rubeiz, PE, M&I Division, TX

UNIVERSITIES

1. **Prof. Tom Iseley, PE**, Purdue University, IN
2. **Prof. Mo Najafi, PE**, CUIRE, Univ. of Texas, Arlington
3. **Prof. Dan Koo, PE**, University of N. Florida

CONTRACTORS

1. **Todd Grafenauer**
2. **Kevin Miller**, Miller Pipeline Co., IN
3. **Richard Crow, PE**, Murphy Pipelines

CONSULTANTS

1. **Luis Aguiar**, Miami-Dade WASD (past), Hazen & Sawyer, FL
2. **John Fishburne, PE**, Charlotte Water (past), Freese & Nichols, NC
3. **Casey Haynes, PE**, H2E, City Utilities, MO (past)
4. **Amster Howard**, B. of Reclamation (past)
5. **Steven Kramer, PE**, COWI North America, NJ, UESI
6. **Ernest Lever**, GTI Energy, IL
7. **Greg Scoby, PE**, Palo Alto, CA (past)

FORMER MEMBERS:

Jessie Allen, PE, Arlington Water Utilities, TX
Alan Ambler, PE, Casselberry, FL (past), AM Trenchless, FL
Dr. Alan Atalah, PE, Bowling Green State Univ, OH
Dr. Sam Ariaratnam, PE, Arizona State University
Joe Castronovo, PE, AECOM (ret.), ASCE UESI, GA
Robert Diamond, PE, City of Palo Alto, CA
Mariana Evora, PE, City of Miami Beach, FL
David Freireich, PE, City of Round Rock, TX
Mike Heitmann, Garney Construction, MO
Todd Jorgenson, City of Austin, MN
Robert Justus, City of Palo Alto, CA

Holly Link, Colorado Springs Utilities, CO
Gordon Mahan, San Antonio Water System, TX
Milton Keys, Indy Water/Veolia, IN
Matthew Klein, Veolia/ Citizens Energy, IN
Dr. Mark Knight, PEng, CATT/Univ. of Waterloo, ON
Ed Lambing, PE, San Jose Water Co., CA
Jonathan Leung, PE, LA Dept. of Water & Power, CA
Ryan MaKaskle, PE, City of Tuls, OK
David Mancini, Mancini and Sons, FL
George McGuire, Ditch Witch, OK
Masa Niya, PE, MUD-Omaha, NE

Dr. Ken Oliphant, PEng, JANA, ON
Rafael Ortega, PE, LAN, TX
Collins Orton, TT Technologies, CA
Fred Oster, PE, City of Boise, ID
Chad Owens, PE, City Utilities, MO
Eric Shaffer, PE, City of Duluth, MN
Dr. Larry Slavin, OPCS, NJ
Dan Smolik, Garney Construction, FL
Dave Stewart, Lago Vista (past), S. HDPE Consulting, TX
Serge Terentieff, PE, EBMUD, CA

MAB-5:

MAB Guidelines for PE 4710 Pipe Bursting of Potable Water Mains

PART 1 – GENERAL

1.1 The MAB-5 Guidelines are for static pipe bursting and to replace potable water mains using HDPE piping systems that conform to AWWA standards. The Guidelines can be adopted in full in conjunction with the **MAB Model Specifications for PE 4710 Buried Potable Water Service, Distribution and Transmission Pipes and Fittings**, or modified by the specifier to fit the project. These Guidelines are for use by utilities while developing project specifications. The guidelines include means and methods which may not pertain for an individual project or situation. These Guidelines can also be utilized for sewer force main replacement. The Owner will assess the potential risk and adjust these Guidelines accordingly.

1.2 DESCRIPTION

Scope – This section specifies high-density polyethylene pipe (HDPE) and fittings for water utility use as indicated on the drawings, and as specified herein. The primary installation method is static pipe bursting. The means and methods, including the testing for acceptance shall conform to all applicable standards as noted herein with the intention of providing a leak-free system to the owner.

1.3 SUBMITTALS

Quality Assurance / Control Submittals: It is imperative the specifier understands and evaluates the risks of performing a static pipe bursting project and understands the importance of requiring and evaluating contractor qualifications.

- i. Minimum Contractor qualifications shall include:
 - a) Being actively engaged with at least _____ projects per year in the installation of HDPE pipe using the static pipe bursting method within the past three (3) years. [Users to specify the appropriate number of projects based on their experience, risk tolerance, sensitivity of project, etc. Typical range of 1 to 3 projects per year]
 - b) Performing _____ feet or more of potable water main replacement using the process of static pipe bursting. Documentation to verify the contractor's experience shall be provided to the Owner. [Users to specify the appropriate footage based on their experience, risk tolerance, sensitivity of project, etc. Typical range of 10,000 to 30,000 ft. NASCO and IPBA require 50,000 ft.]
 - c) Submitting three (3) project reference sheets with municipal contacts including similar scope of work within the past 3 years.
 - d) Submitting Certificate of training endorsed by the static pipe bursting equipment manufacturer.
 - e) Submitting Certificate of HDPE fusion training endorsed by the fusion manufacturer and per ASTM F3190.
- ii. Pipe Bursting Planning

Contractor shall submit a plan to the Owner on a marked-up copy of the Project Drawings showing the Contractor's construction phasing and plans at the Pre-Construction Meeting. Plan details should include:

 - Pit locations for pipe insertion and burst machine location.
 - Pit locations for service re-connects.

- Schedule of when various sections are to be rehabilitated.
- Distances of each pull.
- Isolating points used to seal the system during the pipe burst.
- Temporary services plan and/or pre-chlorination guidelines.
- Staging area for fusing and material storage including moving pipe to burst locations. [Recommend that Users consider Staging areas during design phase which may include parks, alleys, ROW easements, parking lots. Also, include information to describe transportation of pipe strings to limit community impact which could include safety, traffic control, etc.]
- Information about the pipe bursting system to be used such as tonnage and tooling.
- Bursting machine shoring system.
- Risk management plan that covers specific risks.
- Tracer wire

PART 2 – EXECUTION

2.1 INSTALLATION

- A. Pipe Bursting Installation: The pipe bursting operation described within provides guidance on the basic process. It is to be understood that the need to make exceptions or additions to this process are common. These changes are made to accommodate nonstandard conditions. The contractor experience requirements make it reasonable to put the responsibility of devising these exceptions upon the contractor.
- B. Installation of Tracer Wire. The Contractor shall be required to install tracer wire during pipe bursting operations including along all pits for connections. The tracer wire shall be installed simultaneously with the polyethylene piping system. Tracer wire shall be properly spliced at each end connection and each service connection. Care should be taken to adequately wrap and protect wire at all splice locations. No bare tracer wire shall be accepted. Provide Magnesium alloy anode for cathodic protection that conforms to the requirements of ASTM B843. Install tracer wire per local and manufacturer's requirements.
- i. Tracer wire shall be 3/16-inch, 7 x 7 (or stronger) Stranded Copper Clad Steel Extreme Strength with 4,700 lb. break load, or braided stainless steel (A304 or A316), with minimum 50 mil HDPE insulation thickness.
- C. Pit Location and Excavation
- i. Burst pit and insertion pit locations shall be placed such that excavations are minimized. This may be accomplished by placing either or both of these pits at the point of a service connection, valve or hydrant location.
 - ii. Initial burst lengths shall be 400 feet (+/-) 50 feet in length for first 2 bursts to determine soil pipe friction and specific site conditions that may impact bursting lengths. After site specific factors are evaluated, longer burst runs may be performed.
 - iii. All pits shall be shored to ensure worker safety per OSHA or other local regulations.
 - iv. All pits shall be roped off and or covered when not active per OSHA or local regulations to ensure public safety.
 - v. Traffic control shall be accommodated for by Contractor as per the Contract specifications. Safe traffic passage around pit excavations that are located in or adjacent to streets or highways shall meet Right-of-way Department requirements.

Parking of related employee vehicles, trucks and auxiliary and equipment shall be such that congestion and traffic delays are minimized.

- vi. Utilities intersecting the existing pipe shall be exposed using an excavation technique appropriate for the utility. As a general rule, both horizontal and vertical distance between the pipe to be burst and the existing adjacent pipe should be at least two diameters of the replacement pipe. If adjacent utilities are within this area, or the adjacent utility location is unknown, the excavation (Utility Crossing Pit) shall be excavated prior to commencement of bursting. Worker entry shoring is not required, except as determined by OSHA, however appropriate safety precautions should be made.

D. Bursting Machine Location and Shoring: Bursting machines of the static pull style require preparation and planning for the bursting pit that they are to operate from.

- i. Forward face of the Burst Pit or the surface that the machine bears against while pulling back, shall be shored in a safe manner. This shoring shall maintain perpendicular burst machine alignment to the pipe during pullback. Any loss of perpendicular alignment during pull shall result in stopping of the bursting process and improvement of the forward face shoring.
- ii. Rearward shoring shall be provided to react rod thrust forces during payout. While these forces are substantially lower than pullback forces, shoring must be used to stabilize the bursting machine so as to maintain perpendicular alignment of the machine during payout. The weight of the machine cannot be depended on to react thrust forces. Existing pipe at rear face of pit may only be utilized for rearward shoring if scheduled for replacement.
- iii. Pipe face for Cast Iron, Ductile Iron or PVC shall be cut off using a saw or similar device to produce a square face for the bursting machine forward face to bear against. Final separation of cast iron pipe with a wedge may provide a clean face. Existing Pipe shall be removed in sufficient length to accommodate burst machine.
- iv. Burst machine must be positioned so as to have rod centerline at approximate centerline of Existing pipe.
- v. Rod Box delivery and removal between temporary rod storage location and Burst Pit must be accommodated for with appropriate lifting equipment and techniques. Additionally, movement and or placement of lifting machine must be included in Traffic Control plans.

E. Rod Payout Operation

- i. Rod payout is the process of assembling a string of rods and pushing them in a step wise manner from Burst Pit, through the interior of the existing pipe to Insertion Pit.
- ii. Lifting of rod boxes into or out of the Burst Pit shall be performed per OSHA or other applicable requirements with respect to equipment and method.
- iii. Threads shall be cleaned of foreign matter before assembly.
- iv. Counting of Rods during payout, or quantity of rods per box shall be monitored such that the operator is aware of the distance between the burst machine and the lead end of the rod string.
- v. Thrust force should be monitored by the operator. Should an unexpected sudden and significant increase in thrust force be experienced, the process shall be halted. The operator or contractor shall review the results with the Owner to remedy in an attempt to determine if offsets, valves or other features or obstruction exist that may cause the rod string to leave the pipe.
 - A. Front end of the rod string should be located by distance from the Burst Pit. Location should be painted and compared to as built plans.

H. Tooling Removal

- i. Burst Machine Operator shall note rod count and anticipate entry of painted rods into the Burst Pit. As the Pin Joint Connection nears the Burst Machine forward face, the burst is to be halted. Load on the forward face is relieved by reversing the rod direction slightly.
- ii. The Burst Machine Shore Plate is to be removed, allowing the tooling to enter a cage or the hull of the Burst Machine. The tooling string will be disassembled and removed, in sections if necessary until the Product Pipe face has been pulled beyond the face of the Burst Pit. The distance past the face of the Burst Pit shall be at the discretion of the contractor anticipating the length required for connection/fusing.

2.2 DOCUMENTATION FINALIZATION

- A. Within (15) days of completion of the job, all records including manifests, marked up construction plans or documents pertinent to describing the system as installed shall be provided to the Owner.